



Conjectured window line

Polyester powder coated overcill bedded on silicone sealant and secured back to existing window. Gauge of cill and fixing arrangement to suit site conditions and client requirements.

30

WBS cavity spacer track screw fixed into SIPS panel at 300mm centres

SIPS insulated wall panel

25mm drainage cavity behind the render carrier board

WBS approved render carrier board (min. 10mm)

WBS scrim adhesive coat 4-6mm reinforced with WBS alkali resistant glass fibre reinforcing mesh

WBS scrim adhesive 2-3mm finished smooth

WBS silicone primer (colour to clients approval)

WBS silicone finish coat (grain size and colour to clients approval)

drawing. **Overcill detail**

date. July 2009

scale. nts

drawing no. **SIPS-EPSITEC25-RO-08** revision. -

Wetherby Building Systems Ltd



1 Kid Glove Road, Golborne Enterprise Park,
 Golborne, Greater Manchester, WA3 3GS
 Tel: 01942 717100 Fax: 01942 717101
 Web: www.wbs-ltd.co.uk
 E-mail: technical@wbs-ltd.co.uk